

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was a pine post 4 in. sq. 3 ft. long set 18 in. in the ground in a raised mound of earth and scribed 5-555 HF from which:

a fir 10 in. dia. bears S 20 W, 23 ft.

a fir 10 in. dia. bears S 36 E, 238 ft.

DIAGRAM

HF No 5
MS 555
5
1973
645

Description of corner evidence found:

At corner location I found a 28 in. fir with blaze open scribing 5-555 HF BT, no other evidence.

Description of monument and accessories I established to perpetuate the original location of this corner

As the bearing tree was the only evidence, I set a 36 in. long 2 in. galv. iron pipe with 2 in. brass cap using the distance and bearing of the original survey. Set monument in a mound of stone. Cap is marked as shown in the diagram.

New bearing tree:

Set a fir 14 in. dia. bears S 08 E, 22.9 ft. and scribed HF-5-MS 555 BT with a brass tag stamped LS 645.

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad D. Johnson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1984
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:30 o'clock Am., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

10-35-40