

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was a post 6 in. sq. 3 ft. long set 18 in. in ground scribed 2-555 Danae in a raised mound of earth, from which:

a fir 18 in. dia. bears S 20 E, 21.3 ft. scribed 2-555 Danae BT

a fir 16 in. dia. bears S 01 E, 18.0 ft. scribed 2-555 Danae BT.

DIAGRAM

Danae No 2
MS 555

2

1973
645

Description of corner evidence found:

At corner location I found the two bearing trees alive and grown over - did not open.

Description of monument and accessories I established to perpetuate the original location of this corner

As evidence agrees with the original survey I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap at the distances given in the original survey. Placed mound of stone about base. Cap marked as shown in diagram.

New bearing tree:

Set a pine 10 in. dia. bears N 58 E, 18.4 ft. scribed D-2-MS 555 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: *Brad D. Johnson*

Office of *County Surveyor* County of *Baker*
State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *30* day of *November*, 1973, at *9:30* o'clock *A*.m., (signed)
by *Torn Hanley*
(COUNTY OFFICIAL) (DEPUTY)

10-35-41