

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was a pine post 4 in. sq. 3 ft. long set 18 in. in ground in raised mound earth and scribed 3-555 Danae from which:

A pine 40 in. dia. bears N 63 30 E, 43 ft. scribed 3-555-D-BT

A pine 24 in. dia. bears N 58 ~~10~~ W, 58 ft. scribed 3-555-D-BT

A pine 30 in. dia. bears S 60 W, 14 ft. scribed 3-555-D-BT

DIAGRAM

Danae No 3
MS 555

3

1973
645

Description of corner evidence found:

At corner location I found the 40 in. pine dead and on the ground. The other two bearing trees alive and good condition.

Description of monument and accessories I established to perpetuate the original location of this corner

As evidence found agrees with the original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in a mound of stone. Cap marked as shown in diagram.

Set no new bearing trees.

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: *Brad D. Johnson*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
OREGON
JULY 13, 1966
JAMES H. HAMBLETON
645

Office of *County Surveyor* County of *Baker*
State of *Oregon*, I hereby certify that the within instrument was filed in this office
for record on the *30* day of *November*, 19*73*, at *9:30* o'clock *A*.m., (signed)
by *Tom Hamley*
(COUNTY OFFICIAL) (DEPUTY)

10-35-42