

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was an X chiseled on a rock 28 x 14 x 18 in place, from which:

a fir 36 in. dia. bears N 03 W, 18 ft. scribed 4-555 BT.

DIAGRAM

Poorman 4
MS 555

4

1973
645

Description of corner evidence found:

At corner location I found the stone and bearing tree though the bearing to the tree was S 03 E, 18 ft. Opened blaze and found 4-555 BT scribed on face of tree not facing the stone.

Description of monument and accessories I established to perpetuate the original location of this corner

As the location of the stone agrees with the retracement of the lines and it fits the bearing tree notes with the exception that the bearing was reversed, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in a mound of stone with the large stone placed along side the pipe. Cap marked as shown in diagram.

New bearing trees:

a fir 7 in. dia. bears North 22.7 ft. scribed P-4 MS 555 BT with a brass tag stamped LS 645.

a fir 24 in. dia. bears S 79 E, 18.2 ft. scribed P-4 MS 555 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

I hereby certify the above corner monument was re-established as herein above, in October 1973.

Witness: Brad D. Johnson

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 2:30 o'clock A.m., (signed)
by Tom Hambleton
(COUNTY OFFICIAL) (DEPUTY)

10-35-48