

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1903 by Charles H. Fenner US deputy Mineral Surveyor.

Set was a post 4 ft. long 4 in. sq. set 18 in. in the ground with a mound of stone, scribed SC 1-541 from which:

a fir 12 in. dia. bears S 81 25 E, 7.05 ft. scribed BT SC 1-541.

a fir 14 in. dia. bears N 01 W, 28.73 ft. scribed BT SC 1-541.

DIAGRAM

Snow Creek
MS 541

1

1973
645

Description of corner evidence found:

At corner location I found a mound of stone with a rotted post. Both bearing trees are dead and rotted away.

Description of monument and accessories I established to perpetuate the original location of this corner

As evidence agrees with original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap set in a mound of earth and stone. Cap marked as shown in diagram.

New bearing trees:

a fir 6 in. dia. bears S 48 W, 32.9 ft. scribed MS 541 SC-1 BT with a brass tag stamped LS 645.

a fir 8 in. dia. bears S 68 E, 9.2 ft. scribed MS 541 SC-1 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad D. Johnson

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:20 o'clock A.m., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

10-35-59