

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1902, by Arthur Philbrick US deputy Mineral Surveyor.

Set was a post 4.5 ft. long 6 in. sq. set 18 in. in the ground with a mound of stone scribed 1-V 458.

No bearing trees were set.

DIAGRAM

Virgin No 1
MS 458

1

1973
645

Description of corner evidence found:

At corner location I found a mound of stone - no evidence of the post.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence agrees to the original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in a mound of stone. Cap marked as shown in diagram.

New bearing trees:

a pine 9 in. dia. bears S 79 E, 56.4 ft. scribed V-1 MS 458 Rt, with a brass tag stamped LS 645.

a pine 10 in. dia. bears S 45 W, 57.0 ft. scribed V-1 MS 458 BT, with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad O. Johnson

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:20 o'clock A.m., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

10-35-60