

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1902 by Arthur Philbrick US deputy Mineral Surveyor.

Set was a post 4.5 ft. long 6 in. sq. set 18 in. in the ground with a mound of stone scribed V-4 458.

No bearing trees set for this corner.

DIAGRAM

Virgin No 4
MS 458

4
1973
645

Description of corner evidence found:

At corner location I found a mound of stone and a rotted post.

Description of monument and accessories I established to perpetuate the original location of this corner

As evidence agrees with the original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in a mound of stone, placed old post on mound of stone. Cap marked as shown in diagram.

New bearing trees:

Set a pine 8 in. dia. bears N 71 W, 36.4 ft, scribed V-4 MS 458 BT with a brass tag stamped LS 645.

a fir 18 in. dia. bears S 05 E, 28.5 ft. scribed V-4 MS 458 BT. with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad D. Johnson

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:30 o'clock A.m., (signed)
Tom Hanley
(COUNTY OFFICIAL) by (DEPUTY)

10-35-61