

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-15

History of original corner establishment:

Corner was originally established by Herman D. Gradon under GLO contract No. 416, during October, 1881.

The corner was remonumented by L. Myers in 1972.

In September, 1980, under U. S. F. S. contract I was engaged to bring the corner up to U. S. F. S. standards.

DIAGRAM

T10S R35E
S10

1/4 ———— + ————

S15

Description of corner evidence found:

Found Aluminum Cap on 1 1/4" galvanized pipe projecting 8" above the ground and stamped:
Date on the cap, pointing north.

ORLS 699
S10

1/4 ———— + ————

S15

M

1972

Description of monument and accessories I established to perpetuate the original location of this corner:

From which by magnetic declination of N20°E, I perpetuate the corner by adding:

9" tamarac, bears N59°E, 22,8 ft. scribed 1/4 S10 BT.

14" tamarac, bears S50°W, 43,2 ft. scribed 1/4 S15 BT.

Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on the BTs. Placed 54-2 and 54-3 on a steel fence post 5' N48°W and 54-2 on a steel fence post 5' S49°E, from the corner.

I hereby certify that the above work was done to perpetuate the described found corner monument.

Witness: Daniel Rowland

September 12, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of.....January....., 1981.
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-83