

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No.L-9

## History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881. Surveyor General's notes state: "Set a basalt stone 14x12x8 ins. 9 ins. in the ground for 1/4 sec. cor. marked 1/4 on W face: From which: A black pine 10 ins. diam. bears N60°E, 120 lks. dist marked 1/4S BT. A fir 12 ins. diam. bears S60°W, 76 lks. dist. marked 1/4S BT."

## DIAGRAM

T10S R35E  
1/4  
S17 + S16

## Description of corner evidence found:

Found 13x12x8 inch stone set in small mound of stone from which: A dead 22" lodgepole pine bears N62°E, 79.8 ft. scribed 1/4S BT. A 28" fir bears S60°W, 50.0 ft.

## Description of monument and accessories I established to perpetuate the original location of this corner:

T10S R35E  
1/4  
S17 + S16  
OR PLS 1051  
1980

At the center of the above described stone set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 8" in the ground and mound of stone around to cap. Placed marked stone alongside.

From which by magnetic declination of N20°E: A 36" pine bears S55°E, 106.3 ft. scribed 1/4S16 BT. Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on old and new BT. Placed brass washers on new BT stamped PLS 1051. Placed 54-4 on steel fence post 5' south of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland  
Larry Shirley

August 22, 1980

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*  
OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of... County Surveyor... County of... Baker  
Oregon  
State of... I hereby certify that the within instrument was filed in this office  
for record on the 20th day of January, 1981.  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981  
BAKER COUNTY SURVEYOR  
SURVEY NO. 10-35-85