

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-9

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881. Surveyor General's notes state: "Set a basalt stone 20x12x4 ins. 15 ins. in the ground for cor. to secs. 16, 17, 20 and 21. Marked with 3 notches on S and 4 notches on E edges; from which: A black pine 7 ins. diam. bears N25°E, 82 lks. dist. marked T10SR35ES16 BT. A black pine 8 ins. diam. bears S50°E, 20 lks. dist. marked T10SR35ES21 BT. A black pine 8 ins. diam. bears S30°W, 56 lks. dist. marked T10SR35ES20 BT. A fir 14 ins. diam. bears N20°W, 22 lks. dist. marked T10SR35ES14 BT."

DIAGRAM

T10S	R35E
S17	S16
S20	S21

Description of corner evidence found:

Found 20x12x4 inch stone laying in ditch below mound of stone. At center of mound of stone, a white fir snag bears N25°W, 14.4 ft. with some scribing. A 10" down rotten lodgepole poine bears N24°E, 52.0 ft. with full scribe.

Corner falls about 3' north of old mining ditch.

Description of monument and accessories | established to perpetuate the original location of this corner:

T10S	R35E
S17	S16
S20	S21


OR PLS 1051
1980

At the center fo mound set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap. Placed mound of stone beside pipe. From which by magnetic declination of N20°E: A 9" lodgepole pine bears N40°E 29.0 ft. scribed T10SR35ES16 BT. A 9" fir bears S23°E, 42.5 ft. scribed T10S R35ES21 BT. a 15" fir bears S42°W, 77.9 ft. scribed T10SR35ES20 BT. A 12 " lodgepole pine bears N34°W, 10.3 ft. scribed T10SR35ES17 BT. Painted blazes red and 6" red band around. Placed 5403s, 54-4s and brass washers stamped PLS 1051 on BTs. Placed 54-4 on steel fence post 5' East of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Robert Boling
Larry Shirley

July 24, 1980



Office of...County...Surveyor..... County of...Baker
State of...Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...20th day of...January....., 1981.

(COUNTY OFFICIAL)

(DEPUTY)

FILED Jan 20 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-86