

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 0-10-11

History of original corner establishment:

None.

DIAGRAM

T10S R35E
E-NW 1/64

C —+— C
S21

Description of corner evidence found:

None.

Corner falls 200' south of dead end road on south slope.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground and mound of stone around to cap.
From which by magnetic declination of N20°E:
A 12" pine bears S86°E, 124.8 ft. scribed CENWL/64S21 BT. A 9" fir bears S83°W, 29.1 ft. scribed CENWL/64S21 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' east and 54-2 on steel fence post 5' south of the corner.

T10S R35E
E-NW 1/64

C —+— C
S21
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 27, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
5081**

Office of...County...Surveyor..... County of...Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of January....., 1981

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20, 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-91