

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 0-11-12

History of original corner establishment:

None.

DIAGRAM

T10S R35E
W-NE 1/64
C —+— C
S21

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point on north edge of road set 1" X 24" steel bar 2" below the road marked + 5.00 ft. east of reference mark. Set 2 1/2" X 30" galvanized pipe and brass cap marked R.M. 5.00 FT. W. Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E: An 18" pine bears S75°E, 111.8 ft. scribed CW-NE1/64S21 BT. A 14" juniper bears S15°W, 61.0 ft. scribed CW-NE1/64 S21 BT. Placed 54-2 and 54-9 on steel fence post 5' west of reference mark. Placed 54-2 on wood fence post 15' south of the corner. All measurements are from true corner position. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs.

T10S R35E
W-NE 1/64

C —+— C
S21
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 26, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...20th day of...January....., 1981.
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-93