

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. O-P-10-11

History of original corner establishment:

None.

DIAGRAM

T10S R35E
SE-NW
1/64 — S21

Description of corner evidence found:

None.

Corner falls on north edge of old skid road.

Description of monument and accessories established to perpetuate the original location of this corner:

T10S R35E
SE-NW
1/64 — S21
OR PLS 1051
1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 16" fir bears N78°E, 19.7 ft. scribed SENW1/64S21 BT. An 8" pine bears N29°W, 49.7 ft. scribed SENW1/64S21 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' north and 54-2 on steel fence post 5' west of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 27, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of..... County Surveyor..... Baker
State of..... Oregon..... County of.....
I hereby certify that the within instrument was filed in this office
for record on the 20th day of January, 1981
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20, 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-94