

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-11

History of original corner establishment:

None.

DIAGRAM

T10S R35E
C1/4 —+— S21

Description of corner evidence found:

None.

Corner falls about 50' east of small drain.

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 15" tamarac bears N29°W, 45.3 ft. scribed C1/4S21 BT. A 9" tamarac bears S78°E, 30.2 ft. scribed C1/4S21 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-9 on steel fence post 5' east of the corner.

T10S R35E
C1/4 —+— S21
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 27, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of.....County Surveyor.....County of.....Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of January....., 1981
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20, 1981

BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-97