

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-11-12

History of original corner establishment:

None.

DIAGRAM

T10S R35E

WE1/64

C —+— C

S21

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked; Set pipe 8" in the ground and mound of stone around to cap

T10S R35E
WE 1/64

C —+— C

S21

From which by magnetic declination of N20°E:

OR PLS 1051
1980

An 11" pine bears N17°W, 51.3 ft. scribed CWE 1/64 S21 BT.

An 8" pine bears S48°E, 34.4 ft. scribed CWE 1/64 S21 BT.

Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on the BTs. Placed 54-2 and 54-9 on a steel fence post 3' north and 54-2 on a steel fence post 5' east of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 27, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the...20th day of...January....., 1981.

(COUNTY OFFICIAL)

(DEPUTY)

FILED Jan 20, 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-98