

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-15

History of original corner establishment:

None.

DIAGRAM

T10S R35E

CL/4+S22

Description of corner evidence found:

None.

Corner falls about 20' south of snow creek.

Description of monument and accessories I established to perpetuate the original location of this corner:

T10S R35E

CL/4+S22

OR PLS 1051

1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by amgnetic declination of N20°E: A 22" pine bears N18°E, 79.7 ft. scribed CL/4S22 BT. A 10" fir bears N48°W, 42.0 ft. scribed CL/4S22 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-9 on steel fence post 5' east of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 11, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1978
BARRY B. BARBOUR
1051**

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of January....., 1981

.....by.....
(COUNTY OFFICIAL)

.....
(DEPUTY)

Form RC-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-102