

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-Q-13 -14

History of original corner establishment:

None.

DIAGRAM

T10S R35E
NW-SW | S22
1/64

Description of corner evidence found:

None.

Corner falls near the NW corner of large clearing.

Description of monument and accessories | established to perpetuate the original location of this corner:

T10S R35E
NW-SW | S22
1/64
OR PLS 1051
1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E: A 22" pine bears N48°E, 31.7 ft. scribed NWSW1/64S22 BT. A 9" lodgepole pine bears S52°W, 64.3 ft. scribed NWSW1/64S22 BT. painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' west and 54-2 on steel fence post 5' north of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 7, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of...Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of.....January....., 1981

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-106