

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Q-15

History of original corner establishment:

None.

DIAGRAM

T10S R35E
C
S1/16 + S22
C

Description of corner evidence found:

Not Set.

Corner falls 20' south of creek in California Gulch.

Description of monument and accessories | established to perpetuate the original location of this corner:

T10S R35E
C
S1/16 + S22
C
OR PLS 1051
1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 26" in the ground, No rock in the area.

From which by magnetic declination of N20°E:

A 21" tamarac bears S45°W, 45.8 ft. scribed CS1/16S22 BT. An 11" tamarac bears N05°W, 81.8 ft. scribed CS1/16S22 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' south and 54-2 on steel fence post 5' west of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Larry Shirley

August 6, 1980



Barry B. Barbour
OREGON
OCT 17, 1980
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of January....., 1981

..... by
(COUNTY OFFICIAL)

(DEPUTY)

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-111