

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Q-16-17

History of original corner establishment:
None.

DIAGRAM

T10S R35E
E-SE 1/64
C —+— C
S22

Description of corner evidence found:

None.

Corner falls on open flat area.

Description of monument and accessories I established to perpetuate the original location of this corner:

T10S R35E
E-SE 1/64
C —+— C
S22
OR PLS 1051
1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 12" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E: A 9" pine bears N85°E, 39.4 ft. scribe CESE1/64S22 BT. A 16" pine bears N89°W, 45.4 ft. scribed CESE1/64S22 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' south and 54-2 on steel fence post 5' west of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 11, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1979
BARRY B. BARBOUR
1051**

Office of...County Surveyor...County of...Baker
Oregon
State of...Oregon...I hereby certify that the within instrument was filed in this office
for record on the 20th day of...January...1981

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-113