

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Q-R-13

History of original corner establishment:

None.

DIAGRAM

T10S R35E
SS1/64
S21 + S22

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

T10S R35E
SS1/64
S21 + S22
OR PLS 1051
1980

From which by magnetic declination of N20°E:
An 8" fir bears N32°E, 44.9 ft. scribed SS 1/64 S22 BT.
An 11" fir bears S66°W, 23.9 ft. scribed SS 1/64 S22 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on the BTs. Placed 54-2 and 54-9 on a steel fence post 5' west and 54-2 on a steel fence post 3' east of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Larry Shirley

August 6, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of.....January....., 1981.
.....by
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-117