

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-11

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416, during October, 1881. Surveyor General's notes state: "Set a post 3 1/2 ft. long 3 ins. in the ground for 1/4 sec. cor. marked 1/4S on N face, from which: A pine 4 ins. diam. bears N20°W, 11 lks. dist. marked 1/4S BT. A pine 4 ins. diam. bears S40°W, 21 lks. dist. marked 1/4S BT."

DIAGRAM

T10S R35E
S21
1/4 ———
S28

Description of corner evidence found:

None.

Corner was searched for when putting control in and again using positions computed from both section corners. Corner set at single proportionate position.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 26" in the ground. ~~and No rock~~ in the area.

From which by magnetic declination of N20°E: A 6" pine bears S41°W, 21.7 ft. scribed 1/4S28 BT. A 21" tamarac bears N40°W, 58.7 ft. scribed 1/4S21 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on BTs. Placed 54-4 on steel fence post 5' west of the corner.

T10S R35E
S21
1/4 ———
S28
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 28, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon.....I hereby certify that the within instrument was filed in this office
for record on the 20th day of.....January....., 1981
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-119