

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-21

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881. Surveyor General's notes state: "Set a basalt stone 16x6x5 ins. 11 ins. in the ground for cor to Secs. 23, 24, 25 and 26 marked with 2 notches on S and 1 notch on E edges; from which: A fir 8 ins. diam. bears N70°E, 25 lks. dist. marked T10SR35ES24 BT. A tamarack 12 ins. diam. bears S65°E, 40 lks. dist marked T10SR35ES25 BT. A tamarack 12 ins. diam. bears S20°W, 24 lks. dist marked T10SR35ES26 BT. A fir 6 ins. diam. bears N70°W, 56 lks. dist. marked T10SR35ES23 BT."

DIAGRAM

T10S R35E
S23 | S24
S26 | S25

Description of corner evidence found:

Found firmly set 16x7x6 inch stone, clearly marked with 2 notches on S and 1 notch on E edges. From which: A tamarac snag bears S18°E, 15.4 ft., full scribe. A 14" tamarac bears S60°W, 47.6 ft., partial scribing. No trace of north BTs.

Corner falls in small saddle on top of ridge.

Description of monument and accessories | established to perpetuate the original location of this corner:

T10S R35E
S23 | S24
S26 | S25
OR PLS 1051
1980


At the center of above described point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground and small mound of stone around to cap. Placed marked stone at base.

From which by magnetic declination of N20°E: A 24" pine bears N27°E, 71.4 ft. scribed T10SR35ES24 BT. A 20" tamarac bears S17°E, 22.7 ft. scribed T10SR35ES25 BT. An 8" pine bears N26°W, 101.4 ft. scribed T10SR35ES23 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on BTs. Placed 54-4 on steel fence post 5' north of the corner. Old BTs are signed.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 22, 1980



Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of...County...Surveyor..... County of...Baker.....
State of...Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of...January....., 1981

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-275

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-124