

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. V-19

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881, Surveyor General's notes state: "Set a basalt stone 12x8x86 ins. 8 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face; from which: A pine 10 ins. diam. bears N60°W, 118 lks. dist. marked 1/4S BT, A pine 40 ins. diam. bears S80°W, 225 lks. dist. marked 1/4S BT."

DIAGRAM

T10S R35E
S26
1/4 —+—
S35

Description of corner evidence found:

Found 12x8x6 inch stone with small mound around. From which: A 40" pine bears S81°W, 148.1 ft. with grown over blaze. A stump of a down and rotten pine bears N55°W, 78.0 ft. scribed 1/4S BT.

Description of monument and accessories I established to perpetuate the original location of this corner:


At the center of the above stone, set 2 1/2" X 30' galvanized pipe and brass cap marked: Set pipe 22" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E: A 16" pine bears N21°W, 126.3 ft. scribed 1/4S26 BT. Painted blazes red and 6" red band around. Placed 54-3, 54-4 and brass washers stamped PLS 1051 on BTs. Placed 54-4 on steel fence post 5' west of the corner. Old BTs are signed.

T10S R35E
S26
1/4 —+—
S35
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Robert Boling
Larry Shirley

July 22, 1980



Barry B. Barbour
OREGON
OCT. 17, 1978
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 20th day of.....January....., 1981.
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-127

☆ GPO—798-276