

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. V-23

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881. Surveyor General's notes state: "Set a post 3 1/2 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4S on N face; from which: A Tamarack 6 ins. diam. bears N40°E, 14 lks. dist. marked 1/4S BT. A tamarack 14 ins. diam. bears S60°E, 33 lks. dist. marked 1/4S BT."

DIAGRAM

T10S R35E
S25
1/4 ———
S36

Description of corner evidence found:

Found down and rotten 16" tamarac scribed 1/4S BT. Measured N60°W, 21.7 ft. and found rotten wood going vertical in the ground for about 12" from which a down and rotten tamarac stump hole bears N70°E, 9.0 ft.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the center of the above point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground. No rock in the area.
From which by magnetic declination of N20°E: A 16" tamarac bears N12°W, 78.7 ft. scribed 1/4S25 BT. A 9" White Fir bears S29°W, 19.1 ft. scribed 1/4S36 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS1051 on BTs. Placed 54-2 and 54-4 on steel fence post 5' West and 54-2 on steel fence post 5' South of the corner.

T10S R35E
S25
1/4 ———
S36
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Robert Boling
Larry Shirley

July 22, 1980



Office of.....County.....Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..20th day of...January....., 19..81
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-129