

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. X-21

History of original corner establishment:

Corner was originally established by Herman D. Gradon under G.L.O. contract No. 416 during October, 1881. Surveyor General's notes state: "A fir tree 24 ins. diam. which I marked 1/4S on W face for 1/4 sec. cor. from which: A fir 5 ins. diam. bears S85°E, 11 lks. dist. marked 1/4S BT. A fir 8 ins. diam. bears West, 18 lks. dsit marked 1/4S BT."

DIAGRAM

T10S R35E
1/4
S35 + S36

Description of corner evidence found:

Found down and rotten fir with slab scribed 1/4S BT. From which: A 13" fir bears N85°E, 7.4 ft. with grown over blazes. A 24" fir bears N89°W, 13.2 ft. with grown over blazes.

Description of monument and accessories established to perpetuate the original location of this corner:

At center of rotten stump, set 2 1/2" X 30" galvanized pipe and brass cap marked. Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E: A 21" tamarac bears N63°E, 72.0 ft. scribed 1/4S36BT. Painted balzes red and 6" red band around. Placed 54-3, 54-4 and brass washer stamped PLS 1051 on BTs. Old BTs are signed.

T10S R35E
1/4
S35 + S36
OR PLS 1051
1980

I hereby ceritfy that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Larry Shirley

August 22, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of..... County Surveyor..... County of..... Baker
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..20th day of...January....., 1981.
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form RG-7100-57 (9/71)

FILED Jan 20 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35-133

☆ GPO—798-276