


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-25

History of original corner establishment:

Corner was originally established by Herman D. Gradon under GLO contract No. 416 during September, 1881. Surveyors General's notes state: "Set a basalt stone 18x6x5 ins. 12 ins. in the ground for Cor. to Sec's. 1, 12, 6 & 7. Marked with 5 notches on S and 1 notch on N. edges; from which a black pine 6 ins. diam. bears N45°E., 75 lks. dist. marked T10S R35E S6 BT. A black pine 7 ins. diam. bears S80°E., 23 lks. dist. marked T10S R36E S4 BT. A black pine 8 ins. diam. bears S40°W., 58 lks. dist. marked T10S R35E S12 BT. A tamarac 8 ins. diam. bears N70°W., 82 lks. dist. marked T10S R35E S1 BT.




Description of corner evidence found:

Found loose 17x6x5 inch stone clearly marked with 5 and 1 notches. A 16" Lodgepole stump with scribing bears S80°E., 15.2 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:


At the measured point set 2 1/2" X 30" galvanized pipe and brass cap marked; Set pipe 26" in the ground and mound of stone around to cap. Placed marked stone alongside. From which by magnetic declination of N20°E:
 A 8" Fir bears S83°W., 65.0 ft., scribed T10S R35E S12 BT.
 A 13" Tamarac bears N26°W., 85.5 ft., scribed T10S R35E S1 BT.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the BTs.
 Old BTs are signed. Placed 54-4 on steel fence post West of the corner.



I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rwoland

June 30, 1981



Barry B. Barbour
 OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1051

Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 20 day of July....., 1981
 by *Thomas J. Hamley*.....
 (COUNTY OFFICIAL) (DEPUTY)

FILED July 20, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-35-137