

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. T-13

History of original corner establishment:

Corner was originally established by Herman D. Gordon under GLO contract No. 416 during October, 1881. Surveyors General's notes state: "Set a basalt stone 12x10x9 ins., 8 ins. in the ground, for 1/4 sec. cor. marked 1/4 on W. face; from which a pine 30 ins. diam. bears N25°W. 133 lks dist. marked 1/4S; BT. A pine 14 ins diam. bears N25°E. 133 lks dist. marked 1/4S BT."

DIAGRAM

T10S S35E

1/4

S28 + S27

Description of corner evidence found:

Found firmly set 12"x10"x7" basalt stone, clearly marked 4 on west side. From which a 28" pine bears N30°E, 87.9 ft. with 1/4S visible. A 40" pine bears N30°W, 89.7 ft. with grown over blazes.

Description of monument and accessories established to perpetuate the original location of this corner:

At the center of the above stone set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground and mound of stone around to cap. Placed marked stone alongside. From which by magnetic declination of N20°E: BTs have 54-3s and 54-4s. Painted 6" red band around. Placed 54-4 on a steel fence post 5' north of the corner.

T10S R35E

1/4

S28 + S27

OR PLS 1051

1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland

June 29, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...20...day of...July....., 1981
.....by *Thomas J. Henley*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED *July 20, 1981*
BAKER COUNTY SURVEYOR
SURVEY NO. *10-35-144*