

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. T-17

History of original corner establishment:

Corner was originally established by Herman D. Gradon under GLO contract No. 416 during October, 1881. Surveyors General's notes state: "Set a basalt stone 14x10x10 ins. 9 ins. in the ground for 1/4 sec cor. 1/4 on W. face; from which A pine 12 ins diam. bears S40°E., 58 lks dist marked 1/4S BT. A pine 30 ins. diam. bears N80°W., 47 lks dist marked 1/4S BT."

DIAGRAM

T10S R35E
1/4

S27 + S26

Description of corner evidence found:

Found 15"x10"x10" stone firmly set in mound of stone and clearly marked 1/4 on N.W. face. From which a 44" dead Pine bears N79°W., 30.7 ft. scribed 1/4S BT. A 12" dead and down Pine bears S66°E., 41.0 ft. with 1/4S scribing.

Description of monument and accessories | established to perpetuate the original location of this corner:

At center of above point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground and mound of stone around to cap Placed marked stone alongside. From which by magnetic declination of N20°E:

A 9" Fir bears S79°E., 16.8 ft. scribed 1/4 S26 BT.

A 12" Fir bears west, 52.0 ft. scribed 1/4 S27 BT.

Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051. Old BTS are signed. Placed 54-4 on a steel fence post 5' South of the corner

T10S R35E
1/4

S27 + S26
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland

June 29, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the...20... day of...July....., 1981.

..... by *Thomas J. Hendley*.....
(COUNTY OFFICIAL) (DEPUTY)