

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 546 from January 7-11 of 1904. The original notes state that at the corner a marked red fir post 3½' long by 4" square was set 18" in the ground with a mound of rocks from which:

A 10" fir bears N74° 45'W 73.72' marked BT A. No. 1. 4-546.

A 12" red fir bears S53° 15'E 38.30' marked BT A No. 1. 4.546.

The corner was remonumented by Leland Myers in 1972.

DIAGRAM

Aerial No. 1
Cor. 4
Aerial No 1
MS 546

Description of corner evidence found:

Found 2½" alum cap on 1"x30" flanged GIP set loosely in a mound of stones with remains of scribed wood past on mound from which:

A 25" red fir bears N74°W 73⁷ ft. with healed blaze.

A 24" dead and down red fir bears S57°E -38³ ± with faint scribing on healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point, a 2½"x30" alum pipe with 2½" alum cap, marked as shown, was set 6" in the ground with Myers' monument buried horizontally, surrounded by a mound of stone from which:

A 13" Ponderosa Pine bears S66°E -13³ ft. scribed A1-4-546 BT.

Each new bearing tree has a brass washer stamped PLS 1106 nailed to the face of the blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red ring around each bearing tree.

Set steel fence posts Northeast and Southeast of corner and attached signs 54-2 to both posts and sign 54-9 to one post.

Used steel tape and magnetic staff compass with 20° declination, measured to center of bearing trees.

This corner was monumented on July 7, 1983.

WITNESS: Kenneth D. Yokom.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Aerial No. 1
Cor. 4
MS 546
A No. 1
1983
PLS 1106

Office of County Surveyor..... County of Baker
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)