


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 458 during June, 1902. The original notes state that at the corner a 4' long by 4" square marked tamarack post was set 12" in the ground and surrounded with a mound of stone. No bearing trees were established.

DIAGRAM

Greenhorn Cor.5



MS 458

No record of subsequent remonumentation appears in county records.

Description of corner evidence found:

A 6" by 8" wood post set in a mound of stone. The post has visible scribing "MS 458".

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 15" in the ground and surrounded with a mound of stone. Placed wood post on the stone mound. From the corner:

A 11" western larch bears S14 1/2°E-6.4' scribed G-5-458 BT.
A 11" western larch bears S77 1/2°W-19.1' scribed G-5-458 BT.

Each new bearing tree has a brass washer stamped PLS 1106 nailed to the face of the blaze. Attached sign 54-3 and 54-9 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary Northwest and Southeast of corner and attached sign 54-2 to both posts and sign 54-9 to one post.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:

This corner was monumented on July 14, 1983.

Witness: Ken Yokom

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS

1106
Baker

G-Cor.5
MS 458

G.

1983
PLS 1106

Office of.....County Surveyor.....County of.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED May 9, 1984

BAKER COUNTY SURVEYOR

SURVEY NO. 10-35-193