


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

- 80.00 Set basalt stone 18 x 10 x 8 ins. 12 in. in the ground for cor. to secs. 11, 12, 13, 14 marked with 1 notch on E and 4 notches on S edges from which
- A pine 12 ins. in diam. bears N. 20 E. 67 lks. distant marked T. 10 S., R. 35½ E., Sec. 12 B.T.
 - A pine 36 ins. in diam. bears S. 10 E. 24 lks. distant marked T. 10 S., R. 35½ E., Sec. 13 B.T.
 - A fir 14 in. in diam. bears S. 40 W. 53 lks. distant marked T. 10 S., R. 35½ E., Sec. 14 B.T.
 - A tamarack 10 in. in diam. bears N. 85 W. 58 lks. distant marked T. 10 S., R. 35½ E., Sec. 11 B.T.



Description of corner evidence found:

The original rock was found; but three bearing trees were dead and down, scribing legible on two, the third burned. The fourth, standing, was a pine 26 ins. in diam. bearing N. 19 E. 45.3 ft.
Pine overstory, cor. in dense pine and fir understory.

Description of monument and accessories I established to perpetuate the original location of this corner

Set an iron rod 5/8" x 2 ft. 18 ins. in ground on S. of original rock.
Reference tree: a D. fir 26 ins. in diam. bears S. 21 W. 32.3 ft.

REGISTERED
OREGON
LAND SURVEYOR

Leland Lee Myers

JULY 9, 1968
LELAND LEE MYERS
609

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 22 day of July, 1968, at 11 o'clock a.m., (signed)
..... by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)