


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Original Survey by Eugene P. McCornack under contract No. 398 dated July 2 1881  
 Set post 4 ft Long 4 ins square 24 ins in the ground for standard cor to secs 34 & 35 marked SCT10SR35½E on N, S35 on E and S34 on W faces with 2 notches on E and 4 notches on W faces from which  
 A Pine 8 ins diam bears N70° E 41 lks dist marked T10SR35½ES35BT  
 A Tamarack 10 ins diam bears N30° W 8 lks dist marked T10SR35½ES34BT  
 A Tamarack 12 ins diam bears S60° W 20 lks dist marked T11SR35½E S 3 BT



**Description of corner evidence found:**

At the corner location I found rotted wood in the original post hole position  
 S60° W 13.2 ft is a down and rotting 13" Tamarack marked BT  
 N70° E 28 ft is a down and rotting 10" Pine marked S35 BT  
 N30° W 5.3 ft is a root hole where the 10" Tamarack was there is a tree close by but I could see no visible marks.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

In the original post hole I set a 2½"x32" aluminum capped aluminum pipe 24" in the ground in a mound of stone from which  
 A 10" White Fir bears N18° E 13.56 ft marked SCT10SR35½ES35BT nail in W base  
 A 9" White fir bears N85° W 35.56 ft marked SCT10SR35½ES34BT  
 A 12" White Fir bears S44° E 30.03 ft marked T11S R35½E BT nail in N base

MONUMENT STAMPED

S C
T10S R35½E
S34 S35
T 11 S
1983
ORLS 1898

Bearings taken with a staff compass declination 18½° East per 1980 Isogonic chart.

Distances pulled to 60d nail with Brass washer stamped LS 1898 driven in the side center of the bearing trees.

I hereby certify the above monument was re-established as herein described on July 26 1983

*8 August 1983*

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
*Harry C. Hildebrand*  
 OREGON  
 JULY 18, 1980  
 HARRY C. HILDEBRAND  
 1898

Office of... Surveyor..... County of... Baker.....  
 State of... Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)