


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-9

History of original corner establishment:

This corner was originally established by Eugene P. Mc Cornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during July, 1882. The original notes state that at the corner a 20"by10"by6" marked basalt stone was set 15" in the ground from which:

- A 12" pine bears N80°E-40 lks, marked 1/4S BT.
- A 30" fir bears N30°W-6 lks, marked 1/4S BT.



This corner was remonumented by Leland Myers in 1967.

Description of corner evidence found:

Myers' 5/8" by 24" iron pin with 1½" aluminum cap set in a stone mound. The corner has been run over during logging operations. The monument is bent and the original bearing trees are completely destroyed. The monument was still in the ground so the corner position could be identified. A 20" by12"by6" basalt stone, marked "¼" is lying beside Myers' monument.

Description of monument and accessories established to perpetuate the original location of this corner:


Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 20" in the ground and surrounded with a mound of earth and stone. Buried Myers' monument horizontally in the new mound and buried the corner stone in the new mound. From the new monument:

- A 14" white fir bears N24½°E-23.4' scribed 1/4 S9 BT.
- A 19" white fir bears S42½°E-71.2' scribed 1/4 S9 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post South of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:



This corner was remonumented on October 18, 1985.

Witness: Willard Hulick.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of.....County Surveyor..... County of..... Baker.....
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-304-70