


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-15

History of original corner establishment:

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April 1884. The original notes state that at the corner a 12" by 10" by 10" marked basalt stone was set 8" in the ground from which:

- A 24" fir bears N60°E-50 lks, marked 1/4S BT.
- A 6" pine bears S10°W-19 lks, marked 1/4S BT.



In March, 1903, Horace G. Pearson, U.S. Deputy Mineral Surveyor, recovered the corner and used it as Corner No. 1 for the Too Late Placer and the Jordan Placer of MS 509 Amended. The original notes state that Pearson set a 4½' long by 4" square marked pine post, against the South side of the corner stone from which:
A 6" pine bears N2°E-15'.

Too Late Placer Cor 1
Jordan Placer Cor 1

Description of corner evidence found:

- A 8" pine bears S63°E-8.5'.
- Each marked T.L.P. 1-509. B.T. and J.P. 1-509. B.T.

Found a 15" by 8" by 10" basalt stone, firmly set in ground, marked ¼" on North face. Also found Myers' 5/8" by 30" iron pin with 1½" aluminum cap, set against the South side of the corner stone. From the corner stone:
A 8" dead, fallen lodgepole pine bears S10°W-12.5'+ with scribing vis. on double blaze. (Bearing tree from original Barr survey).
A 11" dead, standing lodgepole pine bears S63°E-8.9' with scribing vis. on a partly healed blaze. (Bearing tree from MS 509 AM Survey).
A 10" dead, standing lodgepole pine bears N4°E-15.3' with scribing vis. on a partly healed blaze. (Bearing tree from MS 509 AM Survey).

Also found rotted remains of MS 509 AM wood post lying on the ground.

Description of monument and accessories established to perpetuate the original location of this corner:


At the position of the ¼ corner stone, set a 2½" by 30" aluminum pipe with 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Placed Myers' monument inside of the new monument. Buried corner stone in the new mound and placed wood post on top of the new mound. From the new monument:

- A 8" white fir bears N23½°W-31.3' scribed 1/4 S10-1-TLP-1-JP-509AM BT.
- A 12" western larch bears S0½°E-28.0" scribed 1/4 S15-1-TLP-1-JP-509AM BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post West of corner and attached sign 54-9.

Cap is Marked:

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.



This corner was remonumented on October 16, 1985

Witness: Willard Hulick.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of County Surveyor County of Baker
Oregon
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of , 1985
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)