


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-17

History of original corner establishment:

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April 1884. The original notes state that at the corner a 20"by14"by10" basalt stone, marked with 2 notches on East and 4 notches on South edges, was set 15" in the ground from which:

- A 24" pine bears N50°E-62 lks, marked T10S R35½E S11 BT.
- A 30" pine bears S45°E-34 lks, marked T10S R35½E S14 BT.
- A 8" pine bears S20°W-54 lks, marked T10S R35½E S15 BT.
- A 8" pine bears N70°W-44 lks, marked T10S R35½E S10 BT. Deep Gravel Placer Corner 1



In March 1903, Horace G. Pearson used this corner as Corner no. 1 of the Deep Gravel Placer, MS 509 Amended, and described the corner as follows:

- A 12"by12"by6" above ground basalt stone, marked 1-509, from which:
- A 18" pine bears N18°30'E-49.' scribed D.G.P. 1-509 B.T..
- A 20" pine bears N64°W-25.5' scribed D.G.P. 1-509 B.T..

Description of corner evidence found:

This corner was remonumented by James Hambleton in 1967.

Found Hambleton's 2½" aluminum cap on a 1¼" unflanged iron pipe, set beside a 16"by14"by6" basalt stone with faint chisel work visible. From Hambleton's monument:


- A 20" uprooted pon. pine stump bears N50°E-40.9'+ with no scribing.
- A 20" uprooted pon. pine stump bears S45°E-22.4'± with no scribing.
- A 32" pon. pine bears S20°W-37.2' with scribing vis. on partly healed dbl blaze.
- A 10" dead, standing pon. pine bears N30°W-28.4' with scribing vis. on a partly healed double blaze.
- A rotted, burnt stump bears N18½°E-50'+ with no scribing.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 22" in the ground and surrounded with a mound of earth and stone. Buried Hambleton's monument horizontally in the new mound and buried corner stone in the new mound. The new monument is set at the position of Hambleton's monument. From the new monument:

- A 12" pon. pine bears N80½°E-31.9' scribed T10S R35½E S11-1-DGP-509A BT.
 - A 9" pon. pine bears S29½°E-26.8' scribed T10S R35½E S14-1-DGP-509A BT.
 - A 14" white fir bears N18½°W-15.5' scribed T10S R35½E S10-1-DGP-509A BT.
- New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary South and West of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.



This corner was remonumented on October 24, 1985.

Witness: Willard Hulick.

County Surveyor _____ Baker
 Office of... Oregon _____ County of...
 State of... , I hereby certify that the within instrument was filed in this office
 for record on the... day of... , 19....
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

REGISTERED PROFESSIONAL LAND SURVEYOR

WILLIAM R. WELLS
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

☆ GPO—798-276

FILED 2-3-86
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35½-84