


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

17

**History of original corner establishment:**

This corner was originally established by W.B. Barr, U.S Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 3' long by 3" square marked pine post was set 24" in the ground from which:

- A 8" pine bears S25°E-60 lks, marked 1/4S BT.
- A 10" pine bears N35°W-18 lks, marked 1/4S BT.



The corner was remonumented from original evidence by Leland Myers in 1967.

**Description of corner evidence found:**

Myers' 5/8" by 24" iron pin with 1 1/2" aluminum cap protruding 6" from the ground from which:

A 10" rotted lodgipole pine stump bears N30°W-11.6' with no remaining scribing.

Also found a 4" by 4" wood post marked "1/4 S CS" lying beside the monument.

**Description of monument and accessories established to perpetuate the original location of this corner:**


Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Placed Myers' monumnet inside our new monument and placed wood post on the new mound. From the new monument:

- A 11" western larch bears S35 1/2°E-16.9' scribed 1/4 S14 BT.
- A 17" western larch bears S51 1/2°W-14.1' scribed 1/4 S15 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post South of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:



This corner was remonumented on October 17, 1985.

Willard Hulick.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

**OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106**

Office of County Surveyor..... County of Baker  
 State of Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 10-358-90