


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

N-15

**History of original corner establishment:**

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 16"by12"by10" marked basalt stone was set 11" in the ground from which:

- A 24" pine bears N30°E-29 lks, marked 1/4S BT.
- A 30" pine bears S60°E-30 lks, marked 1/4S BT.



This corner was remonumented by Leland Myers in 1967.

**Description of corner evidence found:**

Myers' 5/8" by 24" iron pin with 1½" aluminum cap protruding 3" from a stone mound. Also found a 18"by16"by12" basalt stone with no marks visible lying beside the monument. From Myers' monument:

A root hole bears N30°E-19.1'±. The uprooted 20" pon. pine bearing tree from this root hole is lying East of the corner with visible scribing on an open double blaze.

A rotted, uprooted pon. pine bears S60°E-19.8'±, with scribing rotted away.

**Description of monument and accessories established to perpetuate the original location of this corner:**


Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 26" in the ground and surrounded with a mound of earth and stone. Placed Myers' monument inside our new monument and buried corner stone in the new mound. From the new monument:

- A 8" pon. pine bears N83½°W-32.0' scribed 1/4 S15 BT.
- A 19" pon. pine bears S10½°E-49.2' scribed 1/4 S22 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post West of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:



This corner was remonumented on October 24, 1985.

Witness: Willard Hulick.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

**OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106**

Office of County Surveyor ..... County of Baker .....  
Oregon

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)