


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

N-23

**History of original corner establishment:**

This corner was originally established by W.B. Barr, U.S Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 14"by12"by10" marked basalt stone was set 9" in the ground from which:



- A 12" pine bears N60°E-94 lks, scribed 1/4S BT.
- A 8" juniper bears S20°E-19 lks, scribed 1/4S BT.

**Description of corner evidence found:**

- A 22" pon. pine bears N63½°E-62.0' with scribing visible on partly healed double blazes.
- A 11" juniper bears S20°E-12.5' with scribing visible on open double blazes.

The corner location was reestablished by measuring record distance from each of the found bearing trees.


**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set a 2½" by 3" aluminum pipe with 2½" aluminum cap 10" in the ground to rock and surrounded with a mound of earth and stone.

Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Cap is marked:

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.



This corner was remonumented on October 22, 1985.

Witness: Willard Hulick.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

**OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106**

Office of..... County Surveyor..... County of..... Baker.....  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 10-35½-100