


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-17

History of original corner establishment:

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 14"by12"by10" marked basalt stone was set 10" in the ground from which:



- A 24" pine bears N60°E-140 lks. marked T1 OS R35½E S23 BT.
- A 24" pine bears S30°E-57 lks, marked T1 OS R35½E S26 BT.
- A 30" pine bears S75°W-108 lks, marked T1 OS R35½E S27 BT.
- A 18" pine bears N25°W-58 lks, marked T1 OS R35½E S22 BT.

Description of corner evidence found:

A 14"by10"by8" basalt stone, protruding 6" from the ground, with no visible marks, from which:

A 32" pon. pine bears S30°E-38.3' with scribing visible on a partly healed double blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Buried corner stone in the new mound. From the corner monument:

- A 12" pon. pine bears S80½°W-30.7' scribed T1 OS R35½E S27 BT.
- A 18" pon. pine bears N69½°W-32.2' scribed T1 OS R35½E S22 BT.
- A 5/8" by 30" iron pin with 1½" aluminum cap reference monument bears N47°E-14.1' marked: RM

SW S23



1106

The reference monument was set because of high road cutbank in this quadrant.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:

T1 OS R35½E

S22 | S23

S27 | S26

1985

PLS 1106

This corner was remonumented on November 21, 1985. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post North of corner and attached sign 54-9.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze.

County Surveyor _____ Baker
 Office of..... County of.....
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells
 OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

☆ GPO—798-276

FILED 2-3-86
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-35½-109