


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-21

History of original corner establishment:

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 12" by 10" by 8" marked basalt stone was set 8" in the ground from which:



- A 12" juniper bears N30°E-52 lks, marked T10S R35½E S24 BT.
- A 36" juniper bears S30°E-54 lks, marked T10S R35½E S25 BT.
- A 24" juniper bears S80°W-31 lks, marked T10S R35½E S26 BT.
- A 10" juniper bears N60°W-121 lks, marked T10S R35½E S23 BT.

Description of corner evidence found:


- A 13" by 8" by 6" basalt stone with faint grooves set in a stone mound from which:
- A 18" juniper bears N31°E-34.3' with scribing visible on a partly healed double blaze.
- A 42" juniper bears S24½°E-35.8' with scribing visible on a partly healed double blaze.
- A 26" juniper bears S85°W-21.6' with scribing visible on a partly healed double blaze.
- A 14" broken topped, green juniper bears N58½°W-82.1' with scribing visible on a partly healed double blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

- Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 8" in the ground to bedrock and surrounded with a mound of earth and stone. Buried corner stone in the new mound. From the new monument:
- A 26" juniper bears N49°W-70.5' scribed T10S R35½E S23 BT.
- New bearing tree has a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post North of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:



This corner was remonumented on November 21, 1985.

Witness: Willard Hulick.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

County Surveyor _____ Baker
 Office of _____ County of _____
 State of Oregon _____, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-35½-111