


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-13

History of original corner establishment:

This corner was originally established by W.B. Barr, U.S. Deputy Surveyor, under his Contract No. 492, dated August 22, 1883, during April, 1884. The original notes state that at the corner a 12" by 10" by 8" marked basalt stone was set 8" in the ground from which:



- A 30" fir bears N70°E-33 lks, marked T10 S R35 1/2 E S27 BT.
- A 30" fir bears S30°E-106 lks, marked T10 S R35 1/2 E S34 BT.
- A 12" tamarack bears S60°W-13 lks, marked T10 S R35 1/2 E S33 BT.
- A 10" tamarack bears N45°W-86 lks, marked T10 S R35 1/2 E S28 BT.

Description of corner evidence found:

A 11" by 8" by 9" basalt stone, firmly set, protruding 4" from the ground, with a groove visible on South side. The corner stone was found under a windfall. From the corner stone:

- A root hole bears N70°E-21.8'±.
- A 40" white fir bears S32 1/2°E-70.0' with healed double blaze.
- A 11" western larch stump bears S65°W-8.6'. The remains of the bearing tree are lying below the corner.
- A 16" dead, standing western larch bears N41°W-56.4' with scribing visible on a partly healed double blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:


Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 22" in the ground and surrounded with a mound of earth and stone. Buried corner stone in the new mound. From the new monument:

- A 12" western larch bears N81 1/2°E-31.5' scribed T10 S R35 1/2 E S27 BT.
- A 11" white fir bears S7°W-12.2' scribed T10 S R35 1/2 E S33 BT.
- A 10" white fir bears N7 1/2°W-7.9' scribed T10 S R35 1/2 E S28 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post North of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:



1985
PLS 1106

This corner was remonumented on November 5, 1985.

Witness: Willard Hulick.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Baker

County Surveyor
Office of..... County of.....
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86
BAKER COUNTY SURVEYOR
SURVEY NO. 10-35E-117