


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by Horace G. Pearson, U.S. Deputy Mineral Surveyor, as part of MS 508, during November, 1902. The original notes state that at the corner a 4 1/2' long by 5" square fir post was set 18" in the ground from which

- A 18" fir bears N82°W-21.1'.
- A 12" fir bears S36°W-31.1'.
- Each marked P.4-508 BT.



Protection Cor. 4

This corner was remonumented by James Hambleton in 1967.

Description of corner evidence found:

A 22" white fir snag bears N82°W-21.0' to face of blaze and 22.1' to centerline with scribing visible on a previously opened blaze.

The corner position was reestablished by measuring record bearing and distance from the found bearing tree, measuring to the face of blaze.

A 2 1/2" aluminum cap on a 1 1/4" by 30" unflanged iron pipe monument by Hambleton is lying on the hillside below the corner position.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 18" in the ground and surrounded with a mound of earth and stone. Buried Hambleton's monument horizontally in the new mound. From the new monument:


- A 8" pon. pine bears S24 1/2°W-63.2' scribed 4-P-508 BT.
- A 15" douglas fir bears N25°W-16.9' scribed 4-P-508 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NE and SE of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:

MS 508



This corner was remonumented on November 4, 1985.

Witness: Willard Hulick.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of County Surveyor County of Baker
Oregon
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of , 1985
 by (COUNTY OFFICIAL) (DEPUTY)

FILED 2-3-86
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-358-156