


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-14

History of original corner establishment:

None.



No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{2}$ " by 30" aluminum pipe with 2 $\frac{1}{2}$ " aluminum cap 24" in the ground and surrounded with a mound of earth and stone, from which:

A 12" Ponderosa Pine bears S 33° W - 46.8', scribed: SW 1/16 S10 BT.

A 17" Ponderosa Pine bears S 3 $\frac{1}{2}$ ° E - 50.6', scribed: SW 1/16 S10 BT.

New bearing trees have a brass washer marked PLS 1106 nailed to face of blaze. Attached signs 54-9 and 54-3, and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary East and South of corner and attached sign 54-9 to one post, and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was monumented on June 13, 1986.

Witnessed by: Willard Hulick.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Cap is marked:

T10S R35 $\frac{1}{2}$ E
SW 1/16
S10
1986
PLS 1106

Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 7-21-86
 BAKER COUNTY SURVEYOR
 SURVEY NO. 10-35 1/2-176