


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-14

History of original corner establishment:

None. Corner never established.



No evidence of corner establishment found in County Records.

Description of corner evidence found:

None. Corner set by survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone, from which:

A 8" White Fir bears N 55½° E - 54.5', scribed: W 1/16 S10 BT.

A 8" White Fir bears S 76½° W - 21.5', scribed: W 1/16 S15 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-9 and 54-3, and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary West and North of corner and attached sign 54-9 to one post, and sign 54-2 to both posts.

Used steel tape and staff compass with 19°E declination, measured to the center of the bearing trees.

This corner was monumented on June 30, 1986.

Witnessed by: Willard Hulick.

REGISTERED PROFESSIONAL LAND SURVEYOR
--

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Cap is marked:

T10S	R35½E
	S10
W 1/16	— — —
	S15

1986
PLS 1106

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 7-21-86
BAKER COUNTY SURVEYOR
SURVEY NO. 10-353-178