


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner never established.



No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone, from which:

A 11" White Fir bears S 28° W - 37.3', scribed: NW-NE 1/64 S21 BT.

A 9" White Fir bears N 74½° E - 17.9', scribed: NW-NE 1/64 S21 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary East and North of corner and attached sign 54-9 to one post, and sign 54-2 to both posts.

Used steel tape and staff compass with 19°E declination, measured to the center of the bearing trees.

This corner was monumented on July 3, 1986.

Witnessed by: Willard Hulick.

| |
|--|
| REGISTERED PROFESSIONAL LAND SURVEYOR |
|--|

William R Wells

| |
|---|
| OREGON JULY 22, 1977 WILLIAM R. WELLS 1106 |
|---|

Cap is marked:
T10S R35½E
NW - NE 1/64
•
S21
1986
PLS 1106

Office of.....County Surveyor..... County of..... Baker.....
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)