

CORNER NO.	MONUMENT	ACCESSORIES
①	FD. 3/4" BRASS CAP IN 2 1/2" GI PIPE SET BY BLM.	FD. ORIGINAL BTS: 22" JUNIPER BEARS N30°E 23.8 FT.; 23" P. PINE BEARS S62°W 72.6 FT.; FD. BLM BT: 31" D. FIR BEARS S70°E 13.9 FT.
②	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 8" D. FIR BEARS N4°E 37.3 FT., SCRIBED 1/4 S31 BT; 6" D. FIR BEARS S70°W 45.1 FT., SCRIBED 1/4 S6 BT.
③	FD. 3/4" BRASS CAP IN 2 1/2" GI PIPE SET BY BLM.	FD. BLM BTS: 11" P. PINE BEARS N67°E 54.1 FT.; 8" D. FIR BEARS S44°E 13.9 FT.; 4" D. FIR BEARS S29 1/2°W 14.9 FT.; 8" D. FIR BEARS N33°W 90.4 FT.
④	FD. 3/4" BRASS CAP IN 2 1/2" GI PIPE SET BY BLM.	FD. ORIGINAL BT: 17" DOWN P. PINE BEARS N12°W 48.8 FT. FD. BLM BTS: 8" P. PINE BEARS S15°E 28.4 FT.; 8" D. FIR BEARS N66°W 21.8 FT.
⑤	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS S85°34'E 1.14 FT. FROM TRUE POSITION. SET 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 7" P. PINE BEARS N24°W 47.0 FT., SCRIBED SS 1/64 S6 BT; 12" P. PINE BEARS S72°E 28.0 FT., SCRIBED SS 1/64 S5 BT.
⑥	FD. ORIGINAL STONE AND 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON.	FD. ORIGINAL BTS: 27" P. PINE BEARS N40°E 22.4 FT.; 30" P. PINE BEARS S80°E 22.4 FT.; 24" P. PINE BEARS S45°W 54.8 FT.; 31" P. PINE BEARS N70°W 35.0 FT.
⑦	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N25°21'E 8.84 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 7" P. PINE BEARS SOUTH 46.8 FT., SCRIBED EE 1/64 S7 BT; 9" ASPEN BEARS N1°W 17.7 FT., BARK SCRIBED EE 1/64 S6 BT.
⑧	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N18°41'E 16.24 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE.	SCRIBED BTS: 14" P. PINE BEARS S15°W 52.5 FT., SCRIBED E 1/16 S7 BT; 13" P. PINE BEARS N52°W 158.2 FT., SCRIBED E 1/16 S6 BT.
⑨	FD. 3" BRASS CAP IN 2 1/2" GI PIPE SET BY BLM.	FD. ORIGINAL BTS: 24" P. PINE BEARS N30°E 71.3 FT.; 24" DOWN P. PINE BEARS S10°W 54.1 FT. FD. BLM BT: 9" JUNIPER BEARS S9°W 33.0 FT. SCRIBED BT: 12" P. PINE BEARS N6°E 123.6 FT., SCRIBED 1/4 S6 BT.
⑩	FD. 3/4" BRASS CAP IN 2 1/2" PIPE SET BY BLM - ROCK MOUND.	FD. ORIGINAL BTS: 27" DOWN P. PINE BEARS N40°E 57.4 FT.; 30" DOWN P. PINE BEARS S55°E 58.1 FT.; 48" DOWN P. PINE BEARS S40°W 64.7 FT.; 13" DOWN P. PINE BEARS S80°E 9.9 FT. FD. BLM BTS: 6" JUNIPER BEARS S37°W 4.0 FT.; 8" D. FIR BEARS N19°W 6.6 FT. SCRIBED BTS: 8" D. FIR BEARS N45°E 74.6 FT., SCRIBED T10S R36E S6 BT; 12" P. PINE BEARS S70°E 41.3 FT., SCRIBED T10S R36E S7 BT.
⑪	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON.	FD. ORIGINAL BTS: 24" P. PINE BEARS N30°E 33.0 FT.; SLIVER WITH SCRIBING IN ROOT HOLE BEARS S80°W 34.3 FT. SCRIBED BTS: 9" D. FIR BEARS N80°W 15.0 FT., SCRIBED T10S R35 1/2 E S1 BT; 8" D. FIR BEARS S70°E 24.3 FT., SCRIBED T10S R36E S6 BT.
⑫	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N68°53'E 14.15 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 12" W. FIR BEARS S12°E 17.5 FT., SCRIBED SW-NW 1/64 S6 BT; 10" P. PINE BEARS S87°W 21.5 FT., SCRIBED SW-NW 1/64 S6 BT.

CORNER NO.	MONUMENT	ACCESSORIES
⑬	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N85°40'E 27.02 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 10" D. FIR BEARS S47°W 32.0 FT., SCRIBED NW-NW 1/64 S6 BT; 15" P. PINE BEARS N25°W 41.3 FT., SCRIBED NW-NW 1/64 S6 BT.
⑭	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS S89°27'E 25.17 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 11" D. FIR BEARS N21°W 20.8 FT., SCRIBED C-N-NW 1/64 S6 BT; 8" D. FIR BEARS N80°E 35.0 FT., SCRIBED C-N-NW 1/64 S6 BT.
⑮	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N59°34'E 18.38 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 9" D. FIR BEARS N8°E 39.7 FT., SCRIBED C-S-NW 1/64 S6 BT; 8" P. PINE BEARS N45°W 30.1 FT., SCRIBED C-S-NW 1/64 S6 BT.
⑯	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N73°25'E 27.06 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 20" D. FIR BEARS S86°W 34.5 FT., SCRIBED C-S-SE 1/64 S6 BT; 8" W. FIR BEARS N1°E 20.9 FT., SCRIBED C-S-SE 1/64 S6 BT.
⑰	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N27°1'E 26.83 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 11" D. FIR BEARS N43°W 31.6 FT., SCRIBED SW-SE 1/64 BT; 11" D. FIR BEARS N15°E 38.3 FT., SCRIBED SW-SE 1/64 BT.
⑱	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N40°51'E 24.24 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 11" D. FIR BEARS N27°E 21.3 FT., SCRIBED C-W-SE 1/64 S6 BT; 8" D. FIR BEARS N17°W 15.1 FT., SCRIBED C-W-SE 1/64 S6 BT.
⑲	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N74°15'E 27.99 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 10" P. PINE BEARS N48°E 56.3 FT., SCRIBED C-E-SE 1/64 S6 BT; 9" P. PINE BEARS N7°E 57.9 FT., SCRIBED C-E-SE 1/64 S6 BT.
⑳	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON BEARS N73°25'E 27.06 FT. FROM TRUE POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 17" P. PINE BEARS S36°W 33.3 FT., SCRIBED SE SE 1/64 S6 BT; 7" P. PINE BEARS N15°W 17.1 FT., SCRIBED SE SE 1/64 S6 BT.
㉑	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 16" D. FIR BEARS S85°W 40.5 FT., SCRIBED C 1/4 S6 BT; 12" D. FIR BEARS N55°W 60.5 FT., SCRIBED C 1/4 S6 BT.

NOTE: ALL NEW BTS ARE FACED AND MARKED PER BLM MANUAL AND IN ADDITION HAVE A BRASS WASHER MARKED LS 1305 NAILED FLUSH IN LOWER BLAZE. ALL BTS ARE PAINTED WITH 6" RED BAND AND ARE TAGGED WITH APPROPRIATE SIGNS. ALL CORNERS SET ARE STAMPED PER BLM MANUAL PLUS THE TOWNSHIP, RANGE, 1982, AND PLS 1305. 6 FT. STEEL POSTS WITH APPROPRIATE SIGNS WERE SET 3 TO 5 FT. FROM ALL CORNERS AS PER CONTRACT. FIELD NOTES ARE IN BOOKS W, X, AND Y, CONTRACT NO. 53-04M3-2-2789.

