

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-10

History of original corner establishment:

None.

DIAGRAM

T10S R36E
SW 1/16
S9

No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap, 24" in the ground and surrounded with a mound of earth and stone, from which:

A 11" Western Larch bears N 13 1/2° E - 32.8', scribed: SW 1/16 S 9 BT.

A 12" Western Larch bears N 50 1/2° W - 42.3', scribed: SW 1/16 S 9 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9, and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary West and North of corner and attached sign 54-9 to one post, and 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was monumented on May 9, 1986.

Cap is marked:

Witnessed by: Willard Hulick

REGISTERED
PROFESSIONAL
LAND SURVEYOR

T10S R36E

SW 1/16

S9

Willard R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

1986
PLS 1106

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)