

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None.

G-11

DIAGRAM
T10S R36E
C 1/4
S9

No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap, 22" in the ground and surrounded with a mound of earth and stone, from which:

A 9" Ponderosa Pine bears N 2° W - 32.2', scribed: C 1/4 S 9 BT.

A 12" Ponderosa Pine bears N 65 1/2° E - 65.0', scribed: C 1/4 S 9 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-9 and 54-3, and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary West and South of corner and attached sign 54-9 to one post, and 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was monumented on May 9, 1986.

Witnessed by: Willard Hulick

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Cap is marked:

T10S R36E

C 1/4

S9

1986

PLS 1106

Office of.....County Surveyor.....County of.....Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)