

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None.

H-9

DIAGRAM

T10S R36E

S 1/16

S8 | S9

No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the
original location of this corner:

Set a 2 $\frac{1}{2}$ " by 30" aluminum pipe with 2 $\frac{1}{2}$ " aluminum cap, 24" in the ground
and surrounded with a mound of earth and stone, from which:

A 12" Ponderosa Pine bears N 60 $\frac{1}{2}$ ⁰ E - 53.2', scribed: S 1/16 S 9 BT.

A 17" Ponderosa Pine bears N 42 $\frac{1}{2}$ ⁰ W - 26.8', scribed: S 1/16 S 8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of
blaze. Attached sign 54-3 and 54-9, and painted face of blaze and 6" red
band around each bearing tree.

Set steel fence posts on National Forest Boundary West and East of corner
and attached sign 54-9 to one post, and sign 54-2 to both posts.

Used steel tape and staff compass with 20⁰E declination, measured to the
center of the bearing trees.

This corner was monumented on May 9, 1986.

Witnessed by: Willard Hulick

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Cap is marked:

T10S R36E

S 1/16

S8 | S9

1986

PLS 1106

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)