

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None.

F-6

DIAGRAM

T10S R36E
NW 1/16
S 8

No evidence of corner establishment found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap, 22" in the ground and surrounded with a mound of earth and stone, from which:

A 12" Ponderosa Pine bears N 0½° E - 8.8', scribed: NW 1/16 S 8 BT.

A 12" Ponderosa Pine bears N 61½° W - 7.2', scribed: NW 1/16 S 8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9, and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence posts on National Forest Boundary West and South of corner and attached sign 54-9 to one post, and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was monumented on May 12, 1986.

Witnessed by: Willard Hulick.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Willi R Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Cap is marked:

T10S R36E
NW 1/16
S 8
1986
PLS 1106

Office of...County...Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)